



350 Summer Street

Structural Steel Detailing Case Study

COMMERCIAL BUILDING | BOSTON, MA

A high-rise commercial steel detailing engagement involving existing-structure coordination, city sequencing zones, and a tight delivery schedule.



3,700

Tonnage



23.6

Weeks



91

Sequences



17

Floors + Roof

PROJECT OVERVIEW

Built for precision in a complex urban steel environment

350 Summer Street is a 17-floor commercial building with a roof level and 2 existing levels. The development is positioned beside an existing building, requiring coordination between new steel, existing columns, existing beams, and varying slab elevations.



17 + Roof
Floors



2
Existing Levels



5
Blocks per Level



11
Core Elevators



PROJECT SNAPSHOT

- Commercial building in Boston, MA
- Typical framing at Levels 4 & 5
- Typical framing at Levels 7–15
- One core wall and two main stair blocks
- All main steel and secondary steel in scope



Scope of Work & Delivery Method

Main steel, secondary steel,
plate girders and davit supports



3,700
tons of steel



5
plate girders
at Level 3



2
plate girders
at Level 6



davit support
posts at
Level 6 & roof



23.6
weeks
schedule



MAIN STEEL DETAILING

Complete detailing of columns, beams, bracings and associated connections in compliance with project specifications and AISC standards.



SECONDARY STEEL DETAILING

Detailing of joists, girders, purlins, stair stringers, handrails and miscellaneous steel to support the primary structure and building systems.



PLATE GIRDER FOCUS

Detailing of 5 plate girders at Level 3 and 2 plate girders at Level 6 including web openings, stiffeners, splices and bearing connections.



DAVIT SUPPORT POSTS

Detailing of davit support posts at Level 6 and roof, including base plates, stiffeners and connection details for marine equipment support.



COORDINATION WITH EXISTING STRUCTURE

Close coordination with existing structure, city sequencing zones and services to ensure constructability and seamless installation.

DELIVERY METHOD




SCHEDULE LENS - 23.6 WEEK PROGRAMME



Model Clarity & Value Delivered

Model clarity supports fabrication and field coordination



Value delivered



Clear representation of the new structure framing and core zones



Improved visibility into sequence-by-sequence detailing progress



Better understanding of interface conditions between new and existing steel



Supports shop drawings, fabrication planning, and erection readiness



Project takeaway

350 Summer Street reflects the type of commercial steel detailing assignment where Moldtek combines technical coordination, sequence control, and schedule discipline to support buildable outcomes for complex urban projects.

Building & Sequencing Logic

91 sequences organized across floors and blocks

Each floor level is divided into 5 blocks (sequences), creating a total of 91 sequences for the entire building. This sequencing approach supports controlled detailing, structured review, fabrication release, and seamless field coordination.




Levels 4 & 5 are typical framing zones.



Levels 7–15 are also typical framing zones.



One core wall with 11 elevators and 2 main stair blocks.



Why the sequencing strategy matters

- ✓ Breaks a large building into manageable detailing packages.
- ✓ Allows typical floor framing to be standardized.
- ✓ Improves coordination between new steel and adjacent existing structure.
- ✓ Supports fabrication and erection planning.

COORDINATION CHALLENGES

Where new steel meets existing structure

Integrating new steel with existing conditions introduced multiple coordination challenges across levels, connections, and interfaces.

01

**Adjacent construction**

The building is being constructed beside an existing building.

02

**Column splice verification**

New columns are spliced onto existing columns, requiring field verification of splice locations.

03

**Level-2 framing complexity**

Level-2 has existing structure and new beams connecting to existing beams.

04


**Slab elevation differences**

Level-2 coordination is more complex due to varying slab elevations.

05

**Existing beam connections**

Connections between new framing and existing beams required careful coordination.

**Detailing implication**

The critical path involved model production, live coordination clarifications, field verification points, and connection interfaces that had to be translated into buildable steel information.